


## Site Readiness Checklist Existing Location

The following items must be received prior to installation/training. ALL ITEMS MUST BE RECEIVED A MINIMUM OF 2 WEEKS PRIOR TO INSTALLATION/TRAINING TO AVOID RESCHEDULING.

## Setup of network and cable runs:

This is the normal setup of a 2 Bay Location. As you can see, all network cabling needs to be run from 1 central location. This is generally next to the main (Server) computer but may be in a different location.



We recommend having 1 extra Cat5e/Cat6 cable run to each location. For instance, if you have a PC, Sticker Printer and Workorder Printer at one station, we recommend having 4 cables. If any issues arise, an extra cable run will be in place. The cost of running an additional cable at the time of installation is minimal. However, running an extra cable after the fact, will be at a much higher cost. Additionally, if you decide to add another Sticker Printer, Workorder Printer, etc. at that location, the extra cable could be used.